



Load-In Help Sheet for the DragonFly 12 x 18.5 ft screen

We need about 50 ft of room to load in
After trailer is in, truck can be removed
It is best to place to left side of stage
Screen rotates so either side will work
Make sure you have 30 ft of clearance above screen

Screen set-up takes about 30 minutes
For a concert we need about 2 hours to set up
and run cables and set cameras



Load-in

- Best to be left of stage (stage right) – however screen rotates
 - Left of stage if your in audience looking at stage
- Screen rotates so left or right of stage will work if need be
- Trailer and truck together are about 50 ft
- Once trailer is set we can remove truck
- Trailer is 8.5 ft wide and with outriggers deployed about 12.5 ft wide
- Best on left side of stage from audience viewpoint
- Need about 25-30 ft of clearance above screen – no trees or wires
- Fairly flat ground

Set up

- About 30 minutes
- With cameras for concert – about 2 hrs

Power

- Shore power or on board generator
- See your contract for option you choose
- We carry 100 ft of cable
- Our cable has cam locks ends – with a bare wire adapter available
- 240, 100 amp single-phase service is required – very important!
- Your electrician to hook up when shore power is used. And disconnect right after event